



SCHEDULE OF ROOMS:

NUMBER	NAME OF THE ROOM	AREA (m2)	CLEAR HEIGHT (mm)	FLOOR FINISH	WALL FINISH	CEILING FINISH	NOTES
POST OFFICE							
1.01	CUSTOMER AREA	18.80	2900	CERAMIC TILES, th.8mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.02	SERVICE AREA	12.12	2900	CERAMIC TILES, th.8mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.03	KITCHEN	5.40	2700	CERAMIC TILES, th.8mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.04	STORAGE	29.73	3290	EPOXY COATING	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	SPIROLL PANEL + ACRYLATE PAINT	STAINLESS STEEL PLINTH PROFILE, th.100mm
1.05	CLEANING ROOM	1.44	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.06	TOILET	1.26	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.07	BATHROOM	1.66	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
MUNICIPAL HALL							
1.08	WC WOMEN	9.29	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.09	BATHROOM WOMEN	3.27	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.10	WC DISABLED WOMAN	3.87	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.11	WC DISABLED MAN	3.87	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.12	BATHROOM MEN	3.18	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.13	WC MEN	6.66	2700	CERAMIC TILES, th.8mm	CERAMIC TILES, th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.14	STORAGE/CHANGING ROOM	15.79	2700	CERAMIC TILES, th.8mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.15	CEREMONY HALL	72.96	6350	WOODEN FLOORING, th. 10mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	WOODEN PLINTH, th.100mm
1.16	HALLWAY WITH WAITING ROOM	52.33	2900	CERAMIC TILES, th.8mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
1.17	SUBMISSION OFFICE	9.72	2900	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
1.18	ELEVATOR	3.47	-	-	-	-	-
1.19	STAIRCASE	13.94	-	CERAMIC TILES, th.8mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	SPIROLL PANEL + ACRYLATE PAINT	CERAMIC PLINTH, th.100mm
SUM OF AREAS		268.76					

LEGEND OF FSB SYMBOLS:

- FIRE COMPARTMENT BORDER
- BORDER OF FIRE DANGEROUS AREA
- P0.02 - II FIRE COMPARTMENT MARKING
- RE 45 DP1 FIRE RESISTANCE OF CEILING
- RE 45 DP1 FIRE RESISTANCE OF CONSTRUCTION
- Δ 21 A PORTABLE FIRE EXTINGUISHER - POWDER 21A
- Δ 27 A PORTABLE FIRE EXTINGUISHER - POWDER 27A
- E = 20 NUMBER OF ESCAPE PEOPLE
- DN19 HYDRANT SYSTEM - HOSE PIPE DN19
- 10 NUMBER AND DIRECTION OF ESCAPE PERSONS
- 10 FIRE EXIT & NUMBER OF ESCAPE PERSONS

0.000 =240,24 m.a.s.l., B.H.S. / COORDINATE SYSTEM S-JTSK

COURSE	DIPLOMA THESIS	FAKULTA STAVEBNÍ posuzování stavů
DRAWN BY	BARBORA HUSÁROVÁ	
SUPERVISED BY	ING. JAN MÜLLER PH.D.	
INVESTOR		
LOCATION	POŘÁDÍ, 687 51 NIVNICE, PARCELS No. 65, 64, 63, 61, 57	PAPER FORMAT 900x420 DATE 01/2025 PROJ. PHASE DPS SCALE 1:100 DRAWING NO. D.1.3.04
PROJECT TITLE	MUNICIPAL CENTRE IN NIVNICE	
BUILDING OBJECT	BO 01 MUNICIPAL CENTRE	
PART	D.1.3 FIRE SAFETY	
DRAWING TITLE:	FIRST GROUND FLOOR PLAN	