



SCHEDULE OF ROOMS:

NUMBER	NAME OF THE ROOM	AREA (m2)	CLEAR HEIGHT (mm)	FLOOR FINISH	WALL FINISH	CEILING FINISH	NOTES
2.01	MAYOR'S OFFICE	23.22	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
2.02	MEETING ROOM	31.05	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
2.03	SECRETARY	12.06	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
2.04	KITCHEN	10.14	2750	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
2.05	STAIRCASE	13.95	-	CERAMIC TILES, th.8mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	SPIROLL PANEL + ACRYLATE PAINT	CERAMIC PLINTH, th.100mm
2.06	ELEVATOR	3.47	-	-	-	-	-
2.07	WC MEN	4.76	2750	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
2.08	WC WOMEN	4.32	2750	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
2.09	BATHROOM MEN	1.99	2750	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
2.10	BATHROOM WOMEN	3.60	2750	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
2.11	HALLWAY	22.77	2750	CERAMIC TILES, th.8mm	CERAMIC TILES, th.8mm	PLASTERBOARD CASSETTE CEILING	CERAMIC PLINTH, th.100mm
2.12	OFFICE	9.90	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
2.13	OFFICE	10.79	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
2.14	PRINTING ROOM WITH STORAGE	10.46	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
2.15	VICE MAYORS OFFICE	13.12	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm
2.16	OFFICE	18.17	2950	VINYL FLOORING, th.3mm	LIME-CEMENT CORE PLASTER WITH STUCCO PLASTER th.15mm	PLASTERBOARD CASSETTE CEILING	PVC SKIRTING BOARD, th.100mm

LEGEND OF FSB SYMBOLS:

- FIRE COMPARTMENT BORDER
- BORDER OF FIRE DANGEROUS AREA
- P0.02-II FIRE COMPARTMENT MARKING
- RE 45 DP1 FIRE RESISTANCE OF CEILING
- RE 45 DP1 FIRE RESISTANCE OF CONSTRUCTION
- △ 21 A PORTABLE FIRE EXTINGUISHER - POWDER 21A
- △ 27 A PORTABLE FIRE EXTINGUISHER - POWDER 27A
- E = 20 NUMBER OF ESCAPE PEOPLE
- H19 HYDRANT SYSTEM - HOSE PIPE DN19
- 35 NUMBER AND DIRECTION OF ESCAPE PERSONS
- 35 FIRE EXIT & NUMBER OF ESCAPE PERSONS

0,000 =240,24 m.a.s.l., B.H.S. / COORDINATE SYSTEM S-JTSK

COURSE	DIPLOMA THESIS		<div><div>T</div><div>FAKULTA STAVEBNÍ pozemního stavění</div></div>
DRAWN BY	BARBORA HUSÁROVÁ		
SUPERVISED BY	ING. JAN MÜLLER PH.D.		
INVESTOR			
LOCATION	POŘÁDÍ, 687 51 NIVNICE, PARCELS No. 65, 64, 63, 61, 57		
PROJECT TITLE	MUNICIPAL CENTRE IN NIVNICE		
BUILDING OBJECT	BO 01 MUNICIPAL CENTRE	PAPER FORMAT	900x420
PART	D.1.3 FIRE SAFETY	DATE	01/2025
DRAWING TITLE:	SECOND GROUND FLOOR PLAN	PROJ. PHASE	DPS
		SCALE	DRAWING NO.
		1:100	D.1.3.05