

LEGEND OF ROOMS				
No.	NAME OF THE ROOM	AREA (m2)	FLOOR FINISH	WALL FINISH
1.01	Kitchen	81,42	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.02	Storage	7,00	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.03	Storage	7,00	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.04	Storage	6,78	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.05	Hallway	19,36	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.06	Disabled Toilet	4,84	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm + C
1.07	Men Toilet	14,21	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm + C
1.08	Women Toilet	16,11	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.09	Staircase Hall	19,26	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.10	Boiler Room	10,20	CERAMIC TILES TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm + C
1.11	Living Room/Kitchen	46,05	LAMINATE FLOOR TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.12	Living Room/Kitchen	36,85	LAMINATE FLOOR TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm
1.13	Bedroom	19,43	LAMINATE FLOOR TH. 8mm	LIME CEMENT CORE PLASTER WITH STUCCO PLASTER TH. 15mm

LEGEND OF MATERIALS

- LOAD BEARING MASONRY WALL POROTHERM 25 EKO PROFI DRY FIX LxWxH 248x249x250 mm
- PARTITION WALL POROTHERM 11.5 PROFI DRY FIX LxWxH 497x249x115 mm
- Concrete blocks - bearing


LEGEND OF LINTELS

- L1 - 3x POROTHERM KP7, LxHxW 1750x238x70mm, PCS 3, LINTEL IS PLACED ON A BED OF CEMENT MORTAR
- L2 - 3x POROTHERM KP7, LxHxW 2500x238x70mm, PCS 4, LINTEL IS PLACED ON A BED OF CEMENT MORTAR
- L3 - 3x POROTHERM KP7, LxHxW 3500x238x70mm, PCS 3, LINTEL IS PLACED ON A BED OF CEMENT MORTAR
- L4 - 1x POROTHERM KP 11,5, LxHxW 1750x71x115mm, PCS 12, LINTEL IS PLACED ON A BED OF CEMENT MORTAR
- L5 - 1x POROTHERM KP 11,5, LxHxW 2500x71x115mm, PCS 12, LINTEL IS PLACED ON A BED OF CEMENT MORTAR
- L6 - 1x POROTHERM KP 11,5, LxHxW 1900x71x115mm, PCS 12, LINTEL IS PLACED ON A BED OF CEMENT MORTAR

NOTES

- WG - WINTER GARDEN, CARPENTER'S PRODUCT, INDIVIDUAL SCHEMES FOR BUILD
- TC - TOILET CABIN, INDIVIDUAL PRODUCT
- ▲ - MAIN ENTRANCE TO THE BUILDING

	X	Y	INITIAL TERAİN	FINAL TERAİN
A	-4889554,00	-16554660,14	174,030 = -0,970	174,230 = -0,770
B	-4889568,81	-16554360,47	173,520 = -1,480	173,720 = -1,280
C	-4889574,61	-16554540,39	173,670 = -1,330	173,870 = -1,130
D	-4889560,39	-16554740,94	174,640 = -0,360	174,840 = -0,160



0.000 = 395,100 m.a.s.l., B.H.S. / COORDINATE SYSTEM S-JTSK		<div>FAKULTA STAVEBNÍ ústav pozemního stavitelství</div>	
COURSE	BACHELOR'S THESIS		
DRAWN BY	ŠIMON MADZIK	PAPER FORMAT 8xA4	
SUPERVISED BY	Ing. JAN MÜLLER, Ph.D.		
INVESTOR	-	DATE 10/2022	
LOCATION	PASOHLÁVKY, 691 22, PARCEL 3163/596		
PROJECT TITLE	GUESTHOUSE IN PASOHLÁVKY	PROJ. PHASE DPS	
BUILDING OBJECT	BO 01 GUESTHOUSE IN PASOHLÁVKY		
PART	D.1.1 ARCHITECTURAL BUILDING SOLUTION	SCALE 1:50 DRAWING NO.	
DRAWING TITLE :	FIRST GROUND FLOOR PLAN		